



- NOTES:**
1. PROVIDE BROOM FINISH TO ALL EXPOSED SURFACES.
 2. CONCRETE SHALL CONFORM TO O.D.O.T. ITEMS 499 AND 511.
 3. CONCRETE SIDEWALKS SHALL BE CONSTRUCTED WITH A MINIMUM THICKNESS OF 4".
 4. PROVIDE A MINIMUM OF 2" EDGING AROUND ALL EXPOSED SURFACES.
 5. PROVIDE A MINIMUM OF 3" OF COMPACTED AGGREGATE BASE (O.D.O.T. 304) UNDER ALL SIDEWALKS.
 6. PERFORM SUBGRADE COMPACTION ON THE AREA UNDER THE PROPOSED SIDEWALK.
 7. INSTALL 1/2" EXPANSION JOINTS EVERY 40' AND BETWEEN NEW AND EXISTING WALKS.
 8. CONCRETE REINFORCEMENT SHALL BE AS DIRECTED BY VILLAGE.